

Polkinghorne Village Buildings 136 Flooring Scope Of Work (Common Spaces and Bedrooms)

Project Start 5/11/2024 – 8/1/2024

**Village West must be completed by 6/10/2024

Furnish and install LVT plus prep and install new cove base, furnish and install 6" Cove Base in entire building – excluding lobby and ceramic tiled areas

- LVT - (Color TBD) 160,000 sq ft
 - LVT Tile + Plank wood look
 - Total Thickness 0.120" (3.0 mm)
 - Wear Layer Thickness: 20 mill (0.50 mm)
 - Edge Treatment: Square Edge
 - Limited Warranty: 20 year
- LVT Adhesive
- 6" Cove Base removal, supply and install new 6" Cove Base
 - Vinyl Cove Base 1/8" roll 40 black toe
 - Wall Base Adhesive
- Slab Prep and LVT Installation – 160,000 Sq Ft

Replace Entry Door thresh-hold wear needed

- Responsible for Removing, protecting, and replacing furniture and any damages incurred in the process.

Questions pertaining to this project

Contact: Julius Gay
POM, Maintenance Superintendent
Florida A&M University
Plant Operations and Maintenance
2400 Wahnish Way Suite 102
Tallahassee, FL. 32307
Office: (850) 599-8054

Post date: Friday, January 19, 2024

Closing date: Friday, January 26, 2024- 4:00 PM